



INDIAN INSTITUTE OF TECHNOLOGY, BOMBAY
ESTATE OFFICE, POWAI, MUMBAI, MAHARASHTRA – 400 076
TEL. 022 2576 4995 E-mail : drestate@iitb.ac.in

IIT Bombay invites digitally signed Technical Bid & Financial Bid for following work from the contractors having similar experience in Central Government Departments / State Government Departments / Central or State Autonomous Bodies / State or Central Public Sector Undertakings & Large Private Organizations. The detail of work is given below:

Sr. No.	Name of Work	Estimated Cost (In Rs.) Incl. 18% GST	EMD (Rs.)	Time Limit	RFX No.
1.	Providing & applying waterproofing treatments at Hostel No. 01,11 & 15. EO/A/HOSTEL/WKS-170/24-25	Rs.56,72,927/-	Rs 1,13,000/-	03 Calendar months	6100002022

Intending bidders need to be registered themselves on IIT Bombay portal i.e. <https://portal.iitb.ac.in/vrp/index.jsp> to get User ID and Password. **View the open tender on <https://ep.iitb.ac.in/irj/portal> Please visit https://portal.iitb.ac.in/vrp/vrp_srm_docs.jsp for configuration process and user manual.** Queries regarding to vendor registration please contact on 022 – 2159 3001(ASC Help-desk) and queries regarding to online Bid submission please contact to +91 82915 56277/6377.

Date and time of submission of tender documents digitally are from 24.01.2025 to 05.02.2025 till 11:15 a.m. Date of opening of **Technical Bid will be 05.02.2025 at 11.30 a.m. and Financial Bid 12.02.2025 (Tentative)**

Interested contractors/agencies are requested to upload Technical bid and Financial bid on the SRM tendering portal of IIT Bombay.

(A) All contractors/agencies should upload technical bid with the following documents on SRM tendering portal, failing to which their tender will be summarily rejected from the tendering process:

- 1) i. Experience of having successfully completed works during the last 7 years ending last day of the month previous to the one in which applications are invited :
Three **completed works** costing not less than the amount equal to 40% of estimated cost put to tender;
OR
Two **completed works**, costing not less than the amount equal to 60% of the estimated cost put to tender
Or
One **completed work** of aggregate cost not less than the amount equal to 80% of the estimated cost.
AND
ii. One completed work of any nature (either part of (i) or a separate one) costing not less than the amount equal to 40% of the estimated cost put to tender with some Central Government Departments / State Government Departments / State or Central Autonomous Bodies / State or Central Public Sector undertakings.
- 2) Detail statement for work completed, work in hand including balance commitment of work should be enclosed for last three year commencing from 1st April and ended with 31st March and contractor should submit his details as per Annexure'A' format with support of xerox copies of work order and work completion certificates, otherwise the bid capacity will not be calculated and his technical bid will be summarily rejected, and no Financial Bid will be opened. (All contractors/agencies are hereby informed that they should upload Technical bid as per format of Annexure "A", changing in format is not allowed).
- 3) Upload a scan copy of the information in respect of **manpower/mandays** for above said work must be given **in undertaking** with official signature and seal/stamp, otherwise tender will be **rejected**.
- 4) Bank Solvency certificate 40% of estimated amount issued within one year from any Nationalized / Schedule Bank from the date of publishing of Tender.
- 5) P. F. registration certificate.
- 6) P. F. challans of last 12months.
- 7) (i) ESIC registration certificate and copies of ESIC challans of last 12months.
OR
(ii) Contractors' all risks insurance (CAR policy) / Mediclaim policy.
- 8) PAN card.
- 9) GST registration certificate.
- 10) Income Tax Return for last 03 years i.e. of **2021-22, 2022-23 and 2023-24**.
- 11) List of Equipment's, Machinery, Tools.
- 12) List of Technical Staff with copies of their Degree/diploma certificate.
- 13) Labour Licence obtained during last 03 years

- 14) The contractors who were empanelled under Estate Office under (2018-23) list need not have to upload Demand Draft. The contractors other than empanel list that are applying for tender need to upload a scan copy of Demand Draft / Pay Order for Rs.1,13,000/-(EMD amount) drawn in favour of "The Registrar, IIT Bombay" on online Tendering Portal.
- 15) Power of Attorney, if any.
- 16) Proof of Constitution: An affidavit in case of Sole Proprietorship, Partnership Deed in case of Partnership Firm, Article of Association in case of Private / Public Limited Companies.
- 17) **Litigation history of the agency** is required to be submitted along with the application. A tender would not be awarded if any inquiry proceeding / criminal case is found pending against the agency.

Note:

Those contractors who do not have documents mentioned above from Sr. No. 1 to 17 need not apply as it is mandatory documents to qualify in technical bids.

Upload all your relevant documents in the serial order mentioned above. It is **advisable** not to make more than **03 folders of 5MB** while uploading documents.

The work will be executed with lowest bidder as per the terms and conditions of work order and tender documents signed by the lowest bidder. (All agencies are requested to upload a scan copy of Terms and Conditions with official signature and seal/stamp on SRM online tendering portal)

The validity of the bids will be valid for 6 months from the date of opening of tender.

If agency fails to submit the above mentioned documents by uploading to the online portal, their technical bid may be rejected.

Litigation history of the agency is required to be uploaded along with the application. Tender would not be awarded if any inquiry proceeding / criminal case is found pending against the agency.

No work will be subletted to third party. If found payment of final bill will not be processed and the contractor's name will removed from the enlistment without giving him further notice.

Contractor's/Agencies/Proprietor's are requested to give Power of Attorney to your representative to deal any matter with any Officers or Staff of IIT Bombay on behalf of you or your agency.

Rates of an estimate are based on CPWD-DSR 2021.

The contractor have to quote his own rates online against each item of work and need to select **N5 tax code** thereafter.

Scan and upload all the above mentioned documents in "**C folder**" of online SRM tendering portal.

IIT Bombay reserve its rights to reject any or all tenders without assigning any reason and without any reference.

No queries will be entertained within 24 hours prior to the opening of the tender. We kindly request all contractors to upload their quotations well in advance of the submission deadline to ensure a smooth and timely process.

Superintending Engineer (I/C)

[Signature]

[Signature]

TO BE UPLOADED ON SRM TENDERING PORTAL WITH FINANCIAL BID

**ANNEXURE 'A' (FORMAT)
TECHNICAL BID**

File No. : EO/A/HOSTEL/WKS-170/24-25

Name of Work : Providing & applying waterproofing treatments to Hostel No.1, 11, & 15.

Name of the Contractor -----

Sr. No.	Name of Client	Name of Works	2021-22 (In Lakhs)	2022-2023 (In Lakhs)	2023-2024 (In Lakhs)	2024-2025 (In Lakhs)	
						Completed	Balance
			-	-	-	-	-
			-	-	-	-	-
Total Amount (In Lakhs)			-	-	-	-	-

Note : Contractor must submit his details as per Annexure 'A' with declaration stating that **he is possessing all the original copies of work orders and experience certificates, it will be produced as and when required to IIT Bombay.** However, if it is found false at later stage, the contractor will be debarred or blacklisted. Whereas, if information is not submitted as per Annexure 'A' format his bid capacity will not be calculated and his tender will be summarily rejected.

Superintending Engineer (I/C)

Signature of Contractor
Name & Address in full

WORKS UNDERTAKING

EO/A/HOSTEL/WKS-170/24-25

To,
Superintending Engineer (I/C)
Indian Institute of Technology,
Powai, Mumbai – 400 076.

Sub : Providing & applying waterproofing treatments to Hostel No.1, 11, & 15.

Dear Sir,

We are hereby quoting all the rates for the attached schedule of short tender of the above mentioned job.

We hereby accept & signed all the General Terms and Conditions and special Conditions of Contract.

The work will be completed within specified time limit of 03 Calendar Months as mentioned in the notice inviting for short tenders.

The following information is required to be provided.

I / We agree to keep the tender open for One Hundred and Eighty (180) days from the due date of its opening / One Hundred and Eighty days from the date of opening of financial bid in case tenders are invited on 2/3 envelope system and not to make any modification in its terms and conditions.

	Male	Female
No. of Unskilled casual labour to be required per day.		
No. of Skilled casual labour to be required per day.		
Total Mandays required for completion of work.		

Thanking you,

Yours faithfully,

Signature of the Contractor
With official Seal / Stamp of the firm

INDIAN INSTITUTE OF TECHNOLOGY BOMBAY

POWAI, MUMBAI – 400076

EO/A/HOSTEL/WKS-170/24-25

ESTATE OFFICE

Name of Work : Providing & applying waterproofing treatments to Hostel No.1, 11 & 15.

Schedule of Work

Sr. No.	Description of work	Qty.	Unit
1	Removing the existing loose and damaged china mosaic flooring with IPS layer waterproofing treatment from terrace area up to any thickness with out making any damages to the roof slab with the use of sharp chisels, levelling and cleaning the roof surface for providing new specialised waterproofing treatment, using step ladder or MS H frame scaffolding lowering down debris without causing dust nuisance and stacking the debris upto a distance at suitable location for taking away outside IIT campus etc. all complete as directed by Engineer In-charge.	170.00	Sqm
2	Dismantling plain cement concrete work including breaking concrete by chiseling, wedging & stacking the debris at suitable location for taking out side IIT campus including step ladder or MS H frame scaffolding etc all complete as directed by Engineer Incharge.	1.00	Cum
3	Removing the existing loose and damaged brickbat coba waterproofing treatment from terrace area/balcony up to any thickness with out making any damages to the roof slab with the use of sharp chisels, levelling and cleaning the roof surface for providing new specialised waterproofing treatment, lowering down debris without causing dust nuisance and stacking the debris at suitable location for taking out side IIT campus etc. all complete as directed by Engineer In-charge.	15.00	Cum
4	Carefully removing the existing damaged cement plaster in patches or any length covering with plastic/tarpaulin wherever required up to any depth without damaging brickwork, plaster in the vicinity, lowering down the debris without causing dust nuisance, & stacking the debris up to a distance at a suitable location to take away out of IIT campus and cleaning the site, including step ladder or MS H frame scaffolding etc. all complete as directed by Engineer In-charge. Note: Proper tools to be used for removal of plaster.	90.00	Sqm
5	Pulling down burnt brick masonry (in cement mortar) with plaster including sorting out serviceable bricks and stacking the same at suitable location as directed and disposing/stacking the debris at suitable location for taking away out of IIT campus including scaffolding etc. all complete as directed by Engineer Incharge.	1.00	Cum
6	Providing & laying cement based water proofing treatment to terrace area / balcony, brick bats laid in required slope to drain the water for any span after cleaning the base surface. Applying a coat of cement slurry admixed with approved water proofing compound and laying the brick bats on bottom layer in C.M 1:5 admixed with approved water proofing compound filling up to half depth of brick bats, curing this layer 3 days, applying cement slurry over this layer joints of brick bats with C.M. 1:3 admixed with approved water proofing compound and finally top finishing with average 20mm thick layer of same mortar finishing the surface smooth with cement slurry admixed with approved water proofing compound including all leads, lifts, curing etc. Covering 5 years' guarantee / warranty on requisite (Rs-100/-)non- judicial stamp paper etc. all complete as directed by Engineer In-charge.	15.00	Cum

Sr. No.	Description of work	Qty.	Unit
7	Providing and laying waterproofing cement concrete (IPS) to terrace at any level as directed to average 50mm thick with 1:1.5:2 cement concrete laid to proper level and slope using river sand including compaction, filling joints, adding recommended waterproofing admixtures as per manufacturer's specifications, marking false marks as directed to give appearances of tiles of 30cm x 30cm or other approved size laid diagonally / square, finishing including neat cement float, testing the treatment by ponding with water for 14 days, providing waterproofing guarantee/warranty for 5 (five) years in requisite (Rs. 100/-) non judicial stamp paper etc. all complete as directed by Engineer In-charge.	170.00	Sqm
8	Providing second class burnt brick masonry with conventional type bricks in cement mortar 1:6 in superstructure including raking out joints and watering etc all complete as directed by Engineer Incharge.	1.00	Cum
9	Providing and laying cement concrete 1:1 ½ : 3 (M-20) using graded stone aggregate 20mm maximum size for foundation, parapets, coping, bed blocks, anchor blocks, band as per details including formwork, compacting, scaffolding, curing etc all complete as directed by Engineer Incharge.	1.00	Cum
10	Providing & applying external waterproof plaster using factory made ready mix polymer cement mortar plaster. i) Providing and rendering the prepared surfaces with new sand faced cement plaster of minimum 20mm thick in two coats by using factory made ready mix polymer modified cement plaster waterproof plaster of approved make (M/s Wall Plast, M/s Fare-Matt) or equivalent. ii) The base coat of minimum 12mm thick using above ready mixed polymer modified mortar plaster to proper plumb level & line including making the plaster surface rough (all as per the manufacturer's specifications) to receive the top finish coat. iii) Applying top/finish coat plaster of minimum 8mm thickness with similar ready mix polymer cement mortar plaster finishing in perfect plumb, line & level so as to obtain fine sand grain finish by using branded approved variety sponge or using mechanised devise including adding additional required quantity of cement for managing richer mix preferable ordinary portland cement 43 grade variety of approved brand at no extra cost, doing regular curing for minimum 7 days iv) The rate shall include providing double scaffolding as per the specifications prescribed at above upto the required height and doing work at all heights and lifts.	90.00	Sqm
11	Providing and fixing machine moulded anodised aluminium sheet of not less than 1.0 mm thick of approved pattern & design, made out of machine cut aluminium sheet over expansion joints on horizontal/vertical surfaces/ceiling floors, fixing in one row on two side of joint shall be done with stainless steel dash fasteners including filling the joint with bitumen filler/ foamboard and sealing the whole with joint sealent of approved company, providing aluminium washers at a staggered pitch, drilling holes in the receiving surface and providing expandable plastic sleeves in holes etc. Complete as directed by Engineer In-charge.	50.00	Sqm
12	Drilling straight and inclined holes upto 300mm depth and upto 20mm dia in concrete / masonry using electrically operated drilling machine and fixing PVC nipple for grouting, conducting water test including scaffolding etc. all complete as directed by Engineer In-charge.	250	Nos.

Sr. No.	Description of work	Qty.	Unit
13	Grouting existing RCC structural members & tile work as per following operations, sealing leak paths with cement mortar & polymer, fixing of nipple, plugging the hole with neat cement paste by ram packing, cleaning including scaffolding etc. all complete as directed by Engineer In-charge. 1) Add Sunflex powder 1.00 kg in one bag of cement of 50 kg with adequate water. 2) Using mechanical means of pressure grouting with the above mix. The pressure shall be 5-10 psi. 3) The grouting to be done into the cracks of ceiling , walls , columns, & beam junctions wherever required . 4) After through grouting sealing the holes with cement slurry etc all complete as directed by Engineer Incharge.	450.00	kg
14	Cutting, demarcating grooves at any height with electrically operated cutter machine between sound and unsound plaster, cracks on external wall, separation cracks including scaffolding, stacking the debris at suitable location etc. all complete as directed by Engineer In-charge.	220.00	Rmt
15	Providing and filling separation crack of 50mm width and 25mm deep with polymer modified cementitious mortar. Demarcating groove, removing plaster / concrete carefully, washing with potable water. Filling polymer modified cementitious mortar in layers of 20mm thick (applying bond coat at every layer) upto profile of concrete in vicinity (composition of mortar: cement 1Kg.: polymer (SBR) of approved manufacturer 15% by wt. of cement : 3Kg silica sand (grading IS 383, zone II, silt content = 0%) over a polymer + cement bond coat including applying making tape on both side of groove, cleaning, finishing to match the plaster in vicinity, scaffolding etc. all complete as directed by Engineer In-charge.	220.00	Rmt
16	Providing and laying waterproofing treatment to terrace surface with 3mm thick APP modified bitumen membrane with polymer reinforcement with overlapping of 75mm along length and 100mm along width of any height including removing the existing waterproofing treatment such as tarfelt, chemical coating etc. without causing damages to the structure, cleaning the surface neatly , removing the dust and loose mortar from the terrace surface and repairing the same with 1:3 cement mortar mixed with waterproofing compound, including applying bitumen based primer @ 0.20Ltr/Sqm and laying the 3mm thick APP modified bitumen membrane, coating with torching method and finishing surface with heat reflective bitumen based silver @ 0.10Ltr /Sqm and covering the whole treatment with five years guarantee / warranty on requisite stamp paper of Rs.100/- etc. all complete as directed by Engineer In-charge.(Make Nilobit/STP/Asian Paint Ltd)	6000.00	Sqm
17	Providing core cutting of any size and depth in reinforcement concrete or any other materials etc. all complete as directed by Engineer In-charge.	5	Nos
18	Providing and fixing P.V.C. rain water pipes 150mm inner dia. and having wall thickness of 2.5 to 3.2mm conforming to I.S. 13592-1992 including with P.V.C. plug bend, necessary fittings such as offsets including fixing the pipe on wall using M.S cleats projecting 25mm to 40mm from face of wall and fixing with clips of approved quality and number, filling the joints with PVC solvent including necessary scaffolding and removing existing pipe etc. all complete as directed by Engineer In-charge. (Submission of warranty for maintenance for a period of 3 years for any leakages /dislocation of pipes joints and replacing the damaged fittings after the completion date on a non-judicial stamp paper of Rs.100/-.)	210.00	Rmt

Sr. No.	Description of work	Qty.	Unit
19	Providing and fixing P.V.C. rain water pipes 110mm inner dia. and having wall thickness of 2.5 to 3.2mm conforming to I.S. 13592-1992 including with P.V.C. plug bend, necessary fittings such as offsets including fixing the pipe on wall using M.S cleats projecting 25mm to 40mm from face of wall and fixing with clips of approved quality and number, filling the joints with PVC solvent including necessary scaffolding and removing existing pipe etc. all complete as directed by Engineer In-charge. (Submission of warranty for maintenance for a period of 3 years for any leakages /dislocation of pipes joints and replacing the damaged fittings after the completion date on a non-judicial stamp paper of Rs.100/-.)	50.00	Rmt
20	Providing and fixing P.V.C. rain water pipes 75mm inner dia. and having wall thickness of 2.5 to 3.2mm conforming to I.S. 13592-1992 including with P.V.C. plug bend, necessary fittings such as offsets including fixing the pipe on wall using M.S cleats projecting 25mm to 40mm from face of wall and fixing with clips of approved quality and number, filling the joints with PVC solvent including necessary scaffolding and removing existing pipe etc. all complete as directed by Engineer In-charge. (Submission of warranty for maintenance for a period of 3 years for any leakages /dislocation of pipes joints and replacing the damaged fittings after the completion date on a non-judicial stamp paper of Rs.100/-.)	35.00	Rmt
21	Disposing debris, loose stones, boulders, concrete pieces etc. collected and stacked as directed including loading in trucks, transporting out of IIT Campus including obtaining permission of BMC competent authorities for disposing off on to their approved locations. The debris are to be removed from site as per instruction of engineer In-charge / his representatives (30% voids will be deducted in case of truck measurement) etc all complete as directed by Engineer Incharge.	30.00	Cum

1) Note : This schedule of work is given for reference purpose only. Contractors are requested to quote your rates online in financial bid.

2) If you will engage labourer 20 or more any day, you have to get labour licence as per contract Regulation & Abolition Act 1970 Rule 1971, and also, you have to keep all such record for inspection to the Principal Employer. If you will engage labour up to 10 Nos. per day, you have to file returns after completion of work as per Building & Construction Act to the Office of Regional Labour Commissioner (Central), Sion, Mumbai.

3) This work is to be executed as per the the clauses mentioned in the tender document signed by you. In addition to the existing safety clause of the tender document a penalty of Rs.5,000/- per case will be recovered from the bills of the particular works, in case any such safety violations are noticed.

4) 01% amount will be deducted from the bills for safety related measures which will be reimburse along with the final bill.

5) Taxes as per government notification time to time.

6) Contractor must pay GST Taxes to concern authority within 30 days time limit after receipt of payment from IIT Bombay & said record must be submitted to IIT Bombay Accounts Section, otherwise action will be taken as deemed fit.

7) If any malpractices / fraud / negligent professional behaviour or any discrepancy / inconsistency / disparity / deviation / disagreement / dissimilarity / mismatch noticed, their contract will be terminated by issuing one month notice by following legal procedure and will be blacklisted and informed to all Government Authorities and Organisations.

Superintending Engineer (I/C)