



INDIAN INSTITUTE OF TECHNOLOGY BOMBAY
ESTATE OFFICE
NOTICE INVITING TENDER

Telephone No. 022 2576-4060, 022-2159-6922 email id drestate@iitb.ac.in

IIT Bombay invites digitally signed Technical Bid & Financial Bid for following work from the contractors having **similar** experience in Central Government Departments / State Government Departments / Central or State Autonomous Bodies / State or Central Public Sector Undertakings & Large Private Organizations. The detail of work is given below:

Sr. No.	Name of Work	Estimated Cost (In Rs.)	EMD (Rs.)	RFX	Duration of contract
1	Renovation of Room No.s 203, 205 & 207 of CSIF Department. EO/A/WORKSHOP/WKS-56/26-27	Rs 80,33,686/- Incl.18% GST	Rs1,60,000/-	6100003065	05 MONTHS

Intending bidders need to register themselves on the IIT Bombay portal i.e. <https://portal.iitb.ac.in/vrp/index.jsp> to get User ID and Password. Please visit https://portal.iitb.ac.in/vrp/vrp_srm_docs.jsp for configuration process and user manual. For queries regarding vendor registration, and configuration process please contact on 022 - 2159 3001 (MDM Help-desk).

All tender documents, forms, etc are available online on <https://www.iitb.ac.in/resources/vendors-tenders> and Central Public Procurement Portal (CPPP) e-tender publishing portal of the Government of India.

Date and time of uploading of tender documents are from 23.06.2026 to 15.07.2026 till 11:15 a.m. Date of opening of Technical Bid will be 15.07.2026 at 11.30 a.m. and Financial Bid 22.07.2026 (Tentative).

All contractors/agencies should submit technical bid with the following documents, failing to which their tender will be summarily rejected from the tendering process:

1) i. Experience of having successfully completed works during the last 7 years ending last day of the month previous to the one in which applications are invited :

Three similar completed works costing not less than the amount equal to **40%** of estimated cost put to tender,

OR

Two similar completed works, costing not less than the amount equal to **50%** of the estimated cost put to tender

Or

One similar completed work of aggregate cost not less than the amount equal to **80%** of the estimated cost.

ii. One completed work of any nature (either part of (i) or a separate one) costing not less than the amount equal to **40%** of the estimated cost put to tender with some Central Government Departments / State Government Departments / State or Central Autonomous Bodies / State or Central Public Sector undertakings.

2) Upload a copy of the information in respect of manpower/mandays for above said work must be given in undertaking with official signature and seal/stamp, otherwise tender will be rejected.

3) P. F. registration certificate.

4) P. F. challans of last 12months.

5) ESIC registration certificate and copies of ESIC challans of the last 12 months (as per the labourers engaged during a particular month). Contractor name should be mentioned in the challans else the agency will be disqualified. OR Contractors' all risks insurance (CAR policy)

6) PAN card.

7) GST registration certificate.

8) Income Tax Return for **assessment year** i.e. of **2023-24 ,2024-25 & 2025-26**.

9) List of Equipment's, Machinery, Tools.

10) List of Technical Staff with copies of their Degree/diploma certificate.

11) **Submit** DD/FDR/BG of Rs. 1,60,000/- in the name of "The Registrar, IIT Bombay" **before the opening of Technical Bid.** Contractors are also requested to upload a scanned copy of it to the online Tendering portal.

12) Power of Attorney, if any.

13) Proof of Constitution: An affidavit in case of Sole Proprietorship, Partnership Deed in case of Partnership Firm, Article of Association in case of Private / Public Limited Companies.

14) **Litigation history** of the agency is required to be upload along with the application. A tender would not be awarded if any inquiry proceeding / criminal case is found pending against the agency. If there is no enquiry then undertaking has to be uploaded in the format given.

15) Bank Solvency certificate 40% of estimated amount issued within one year from any Nationalized / Schedule Bank from the date of publishing of Tender.

16) Detail statement for work completed, work in hand including balance commitment of work should be enclosed for last three year commencing from 1st April and ended with 31st March and contractor should upload his details as per **Annexure'A'** format with support of xerox copies of work order and work completion certificates, otherwise the bid capacity will not be calculated and his technical bid will be summarily rejected.

Terms & Conditions :

The documents listed below from Sr. No. 1 to 16 is mandatory for qualification in the technical bid evaluation process.

Select 'N5' tax code for 18% GST and upload all the above mentioned documents in "C folder" of online SRM tendering portal.

The work will be executed with lowest bidder as per the terms and conditions of work order and tender documents signed by the lowest bidder.

The validity of the bids will be valid for 6 months from the date of opening of tender.


No work will be subletted to third party. If found payment of final bill will not be processed and the contractor's name will be removed from the enlistment without giving him further notice.

The rates are prepared from CPWD DSR 2023 & Rate Analysis.

Contractors are strictly prohibited from engaging in any correspondence related to tender documents with anyone other than the Tender Section. Any violation will result in disqualification from all future tenders.

No queries will be entertained within 24 hours prior to the opening of the tender. We kindly request all contractors to upload their quotations well in advance of the submission deadline to ensure a smooth and timely process.

IIT Bombay reserve its rights to reject any or all tenders without assigning any reason and without any reference. IIT Bombay reserves the right to request a detailed justification of the quoted rates from the lowest bidder, if deemed necessary by the Engineer-in-Charge. Should the justification provided by the bidder be considered unsatisfactory or unsubstantiated, the Engineer-in-Charge shall have full authority to reject the bid, irrespective of it being the lowest.

b 
22/6/26
Superintending Engineer (I/C)
Dir  19/6
Gen  1/2
mtc

DECLARATION

- (a) We are not involved in any litigation that may have an impact of affecting or compromising the works as required under this tender.
- (b) We are not black-listed by any Central/State Government/Public Sector Undertaking in India.
- (c) We hereby confirm and declare that M/s [Company Name] does not have any Litigation / Arbitration History with any Government department, Public Sector Undertaking (PSU), or Private Sector agency for works executed during the **last 5 years**.
- (d) I/we undertake that the documents submitted are genuine/authentic and nothing material has been concealed therefrom and that I/we are not debarred by any Government organization and are competent to have the contract. I/we understand that the contract is liable to be cancelled, if found to be having obtained, through fraudulent means/concealment of information.

(Signature of Authorized Signatory)

Name of the bidder:
Complete Address:

Address (Works), if

any: Contact Nos.

INDEX SHEET

Sr. No.	Content	Page No. From - To
1	Experience of having successfully completed works during the last 7 years ending last day of the month previous to the one in which applications are invited : Three similar completed works costing not less than the amount equal to 40% of estimated cost put to tender, OR Two similar completed works, costing not less than the amount equal to 50% of the estimated cost put to tender Or One similar completed work of aggregate cost not less than the amount equal to 80% of the estimated cost.	
2	Submit a copy of the information in respect of manpower/mandays for above said work must be given in undertaking with official signature and seal/stamp.	
3	Bank Solvency certificate 40% of estimated amount issued within one year from any Nationalized / Schedule Bank from the date of publishing of Tender.	
4	P. F. registration certificate.	
5	P. F. challans of last 12months.	
6	ESIC registration certificate and copies of ESIC challans of the last 12 months (as per the labourers engaged during a particular month).Contractor name should be mentioned in the challans else the agency will be disqualified.ORContractors' all risks insurance (CAR policy)	
7	PAN card.	
8	GST Registration certificate	
9	Income Tax Return for assessment year i.e. of 2023-24 ,2024-25 & 2025-26.	
10	List of Equipment's, Machinery, Tools.	
11	List of Technical Staff with copies of their Degree/diploma certificate.	
12	Earnest Money Deposit	
13	Power of Attorney, if any.	
14	Proof of Constitution: An affidavit in case of Sole Proprietorship, Partnership Deed in case of Partnership Firm, Article of Association in case of Private / Public Limited Companies.	
15	Litigation history of the agency is required to be submitted along with the application. A tender would not be awarded if any inquiry proceeding / criminal case is found pending against the agency.If there is no enquiry then undertaking has to be submitted in the format given.	
16	Annexure 'A'	
17		
18		

Signature & stamp of the Contractor

TO BE UPLOADED ON SRM TENDERING PORTAL WITH FINANCIAL BID

**ANNEXURE 'A' (FORMAT)
TECHNICAL BID**

File No. : EO/A/WORKSHOP/WKS-56/26-27

Name of Work : Renovation of room no's 203, 205 & 207 of CSIF department.

Name of the Contractor -----

Sr. No.	Name of Client	Name of Works	2022-23 (In Lakhs)	2023-2024 (In Lakhs)	2024-2025 (In Lakhs)	2025-2026 (In Lakhs)	
						Completed	Balance
			-	-	-	-	-
			-	-	-	-	-
Total Amount (In Lakhs)			-	-	-	-	-

Note : Contractor must submit his details as per Annexure 'A' with declaration stating that **he is possessing all the original copies of work orders and experience certificates, it will be produced as and when required to IIT Bombay.** However, if it is found false at later stage, the contractor will be debarred or blacklisted. Whereas, if information is not submitted as per Annexure 'A' format his bid capacity will not be calculated and his tender will be summarily rejected.

6 
22/6/24
Superintending Engineer (I/C)


MIC

Signature of Contractor
Name & Address in full

WORKS UNDERTAKING

EO/A/WORKSHOP/WKS-56/26-27

To,
Superintending Engineer (I/C)
Indian Institute of Technology,
Powai, Mumbai – 400 076.

Sub : Renovation of rooms no's 203, 205 & 207 of CSIF department.

Dear Sir,

We are hereby quoting all the rates for the attached schedule of short tender of the above mentioned job.

We hereby accept & signed all the General Terms and Conditions and special Conditions of Contract.

The work will be completed within specified time limit of 5 months as mentioned in the notice inviting for short tenders.

The following information is required to be provided.

I / We agree to keep the tender open for One Hundred and Eighty (180) days from the due date of its opening / One Hundred and Eighty days from the date of opening of financial bid in case tenders are invited on 2/3 envelope system and not to make any modification in its terms and conditions.

	Male	Female
No. of Unskilled casual labour to be required per day.		
No. of Skilled casual labour to be required per day.		
Total Mandays required for completion of work.		

Thanking you,

Yours faithfully,

Signature of the Contractor
With official Seal / Stamp of the firm

INDIAN INSTITUTE OF TECHNOLOGY BOMBAY
POWAI, MUMBAI, MAHARASHTRA - 400 076

EO/A/WORKSHOP/WKS-56/26-27

ESTATE OFFICE

Name of work:- Renovation of Room no's 203, 205 & 207 of CSIF Department.

Sr. No.	Description of work	Qty.	Unit
1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead of area beyond 3 sq. metres	11.00	Nos
2	Dismantling PCC, IPS layer of any thickness above brick bat coba(till naked slab if brickbat coba is absent) from terrace floor/chajjas of building carefully without damaging the existing brickbat(if present), levelling the surface, cleaning the site, stacking the debris outside at designated spot etc. complete.	2.00	m3
3	Dismantling burnt brick masonry (in cement mortar) with plaster including sorting out serviceable bricks and lowering down debris, stacking the same and debris separately upto a distance of 50 metres or spreading the debris as directed.	13.00	m3
4	Removing the old cement concrete or any type of tiles/ door, window sill/ platform stone slab from floor / wall carefully including levelling the surface, cleaning the site, lowering down the debris from any height by manual or mechanical means and stacking the debris up to 50 mtr distance etc. complete.	97.00	m2
5	Removing existing waterproofing treatment from the WC/Bathroom up to the mother slab including tiles, plaster etc. of any thickness without damages to structure, pipes using electrically operated cutting tools, leveling and cleaning the surface, including lowering down the debris and stacking the same at a distance of 50mtr etc. all complete as directed.	20.00	m3
6	Removing soling without dust nuisance including sorting out the stone chips and debris separately and stacking upto distance of 50 metres as directed.	1.00	m3
7	Disposing debris, loose stones, boulders, concrete pieces broken etc. collected and stacked as directed including loading in trucks, transporting out of IIT Campus including obtaining approval from Government/ private land owners for disposing off on to their approved location. The contractor will be solely responsible for disposing debris out of campus and the debris are to be removed from site within 72 hours from stacking (30% voids will be deducted from actual measurement for debris, loose stones, boulders, concrete pieces).	67.00	m3
8	Dismantling Reinforced cement concrete work including breaking concrete by chiselling, wedging including scaffolding, covering area with jute kantan to avoid spreading of dust etc., stacking the debris upto a distance of 50 metres as directed.	1.00	m3
9	Dismantling existing brickbat coba waterproofing from the terrace up to mother slab or as per the requirement as directed by Engineer in charge without damaging the RCC slab carefully using electrically operated tools including lowering down the debris and stacking the same upto 50 mtrs from the working site etc. all complete as directed.	1.00	m3

10	Providing and laying in position ready-mixed or machine batched or machine mixed design mix M-25 (1:1:2) grade cement concrete (with minimum cement content 330Kg/Cum) for all work above plinth level upto any floor level for reinforced cement concrete work, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per relevant IS code to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge including compacting, roughening the surface if special finish is to be provided, casting cubes and testing etc. completed as directed.	1.00	m3
11	Providing and laying cement concrete 1:1 1/2: 3 (M- 20) plinth level to upto any floor using sand as fine aggregate and graded stone aggregate 20mm maximum size for foundation, coping and bedding, levelling, dewatering by any means, compaction, finishing, curing etc. complete all as directed.	1.00	m3
12	Centering and shuttering including strutting, propping etc. and removal of form for all heights :Lintels, beams, plinth beams, girders, slabs, bressumers and cantilevers,etc	1.00	m2
13	Laying dry trap / rubble stone soling of required thickness including hand packing and compacting in proper level all complete as directed by Engineer-in-charge.	1.00	m3
14	Providing second class burnt brick masonry with IS approved quality well burnt bricks having crushing strength of 35 kg. / square cm. and maximum water absorption of 20% in cement mortar 1:6 in superstructure including striking joints, racking out joints, watering etc. complete as directed.	13.00	m3
15	Providing and fixing not less than 16 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut Granite (area of slab upto 0.50 m2) for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.	28.00	m2
16	Carefully removing internal or external plaster in patches or any length without damaging structure brickwork in the vicinity by using electric cutting tools including cutting a groove first to demarcate exact area of damage taken place stacking the debris with in 50 meter, cleaning the site etc. complete. including covering the furniture, floor, windows and partitions with plastic sheets while chipping including scaffolding. Note:- a) No extra payment shall be made for extra thickness removed. b) Proper tools to be used for removal of concrete and it should be seen by contractor no damage on the other side / near by area will be taken place and if required other portions are to be checked by the contractors with respect to the damage before commencement of the work. c) The area in vertical plane shall be measured.	67.00	m2

17	Cleaning of reinforcement from rust from the reinforcing bars to give it a total rust free steel surface by using alkaline chemical rust remover of approved make with paint brush and removing loose particles after 24 hours of its application with wire brush and thoroughly washing with water and allowing it to dry, including working platform / stepladder all complete as per direction of Engineer-In-Charge	706.00	m2
18	Chipping of unsound/weak concrete material from slabs, beams, columns etc. with manual Chisel and/ or by standard power driven percussion type or of approved make including tapering of all edges, making square shoulders of cavities including cleaning the exposed concrete surface and reinforcement with wire brushes etc. and disposal of debris for all lead and lifts, including working platform / stepladder all complete as per direction of Engineer-In-Charge	706.00	m2
19	Providing and applying an effective bond coat of Polymer (SBR) approved by IITB and cement in the proportion of 1:1 by using brush in multiples coats as required to accommodate the whole thickness of polymer modified mortar wherever required etc. on the surface of old concrete / repaired concrete Polymer (SBR) of approved manufacturer. Note: The actual consumption of polymer shall be measured for payment on weight basis. Challans of authorized dealer will be verified.	1,412.00	Kg
20	Providing and Placing in position readymix polymer mortar manufacture by Dr. Fixit, Sunanda, Roff, MC Bouchmeyer, Chembond and adding water in the proportion of 1:0.14 (polymer mortar : water) in prepared grooves / cracks of the concrete court in layers as directed including mixing the polymer mortar with water using forced action mixer mild curing with water for 3 days and finishing the surface in all respect including scaffolding etc. Complete. (Payment will be paid for the actual quantity of polymer mortar PX used on weight basis. Challans of authorised Dealer will be verified etc all complete as directed by Estate office).	12,499.00	Kg
21	Providing internal cement plaster 20mm thick in a single coat in cement mortar 1:4 without neeru finish to concrete or brick surfaces in all positions with the use of step ladder and curing complete.	294.00	m2
22	Providing and applying white cement based Birla make wall care putty of average thickness 1mm, over plaster/ concrete surface in proper line / level to prepare surface even and smooth for including preparing the wall surface for the application of wall care putty etc. complete as directed.	446.00	m2
23	Providing sand face plaster externally using approved screened sand in all positions including base coat of 15mm thick in cement mortar 1:4 using water proofing compound per cement bag as per manufacturer specification and curing the same for not less than two days and keeping the surface of base coat rough to receive the sand faced treatment not to exceed 8mm thick in cement mortar 1:4 using water proofing compound per cement bag as per manufacturer specification as per manufacturer specification, finishing the surface by taking out grains and curing for 14 days, scaffolding etc. complete.	644.00	m2
24	Providing temporary steel supports such as tubular steel props 50mm dia, as required for supporting system till the repaired work of the beam, column, slab, chajja, etc. work completed in all respects as directed and when required in any floor of any height inside and outside of the building and removing the supporting system as directed without damaging the structure.	50.00	No

25	Providing and applying HILTY HIT-HY RE 500 injection in RCC including fixing in steel diameter 8mm to 12mm & length 4" to 6" reinforce bars including drilling hole as per manufacturer specifications, blowing out the hole and finishing etc. Complete as directed.	280.00	Nos
26	Providing and laying super fluid micro concrete of approved manufacturer at any floor after reinforcement treatment coat including mixing with 10mm to 5mm size quartz aggregate in the ratio of 1 part Pidilite make roff crete to 0.75 part of quartz aggregate by weight providing marine plywood formwork in line and level, cleaning, curing etc. complete.	19,826.00	KG
27	Making holes having 4" diameter in the Horizontal RCC slab without damaging the other part of slab and reinforcement up to slab thickness using core cutting tools with labor and etc. completed as directed.	32.00	Nos
28	Providing and fixing Jute kantan (Tarat) screen to the scaffolding of external wall for any height of building, removing the same after the work is over etc. complete	500.00	m2
29	Providing and fixing Ist quality ceramic wall tiles conforming to IS: 15622 of size 300mmx450mm or 300mm x 600mm as directed by Engineer-in-charge having thickness not less than 5mm, of approved make, in all colours, shades of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement plaster /mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade	89.00	m2
30	Providing and laying Glazed Vitrified tiles Matt/Antiskid finish of size not less than 600x600 with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade, laid on 20 mm thick cement mortar 1:4 (1 cement: 4 coarse sand) jointing with grey cement slurry @3.3 kg/sqm including grouting the joints with white cement and matching pigments etc. The tiles must be cut with the zero chipping diamond cutter only . Laying of tiles will be done with the notch trowel, plier, wedge, clips of required thickness, leveling system and rubber mallet for placing the tiles gently and easily.	49.00	m2
31	Providing and fixing two mm thick PVC flooring (vinyl flooring) in roll or tile form manufacture by armstrong of approved shade and in approved pattern on smooth and leveled bed, fixing the flooring as per manufacturer specifications etc. complete.	46.00	m2
32	Providing and fixing solid core flush door in single or double leaf 32mm thick of commercial type of exterior grade, approved commercial plywood facing both side without glazing and venetians, all necessary beads, moulding and lipping, 300mm long 2 nos. decorative type S.S handles for each shutters, 8" long stainless steel tower bolt 1 no for each shutter, 6 lever Godrej mortise lock with triplicate keys and other required fittings etc. complete (without frame). (fittings will be approved by Engineer in charge before fixing)	6.00	m2
33	Providing and fixing ISI marked and IITB approved make hydraulic door closer to door shutter including making proper adjustment for smooth operation etc. complete.	5.00	Nos

34	Providing & fixing 1mm thick designer laminate of approved brand and pattern wherever required including, making necessary grooves wherever required as per standard practice with all required fittings and fixtures etc. complete as directed.	22.00	m2
35	Providing and fixing in position tor steel bar having grade Fe-500D or more for reinforcement of various diameters for R.C.C. footings, foundations, slabs, beams, columns, canopies, staircases, chajjas, lintels, pardies, coping, fins, dowel bars with sleeve, tie bar, any other required work etc. as per detailed designs, drawings and schedules including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required completed as directed.	1,051.00	Kg
36	P/f 5mm thick glass for vision panel in door including making necessary cutting in the door of required size with necessary teakwood moulding and melamine polish on moulding all complete as directed.	3.00	m2
37	Providing and applying one coat of seal cement primer IITB approved brand, Including scrapping the surface, filling the holes with lambi/palti, covering the floor, windows, instruments with clean plastic sheet, including working platform / stepladder during painting etc. complete.	446.00	m2
38	Providing and applying roller finish plastic emulsion paint of IITB approved manufacturer and of desired colour and shade to old / new ceiling & wall surfaces in two coats with covering the floor, windows, instruments with clean plastic sheet including working platform / stepladder during painting (excluding priming coat) complete.	446.00	m2
39	Providing and applying Acrylic distemper of IITB approved manufacturer and of desired colour and shade to old / new surfaces in two or more coats , preparing the surfaces (excluding priming coat), covering the floor, windows, instruments with clean plastic sheet, use of working platform / stepladder during painting complete.	97.00	m2
40	Providing and fixing without anodising or powder coating aluminium section for door frame, windows, partitions and any other require work etc. of required size including fixing with required fittings such as screws and other required fittings including fixing in proper alignment, rectifying all damaged, P/F wood inside frame for fixing hinges etc. completed as directed.	10.00	Kg
41	Providing and fixing 15 micron anodized/ powder coated aluminium section for door frame, windows, partitions and any other require work etc. of required size including fixing with required fittings such as screws and other required fittings including fixing in proper alignment, rectifying all damaged, P/F wood inside frame for fixing hinges etc. completed as directed.	25.00	Kg
42	Providing and fixing in position shutter in sliding window using aluminium section for bottom and top member of size 40 mm x 18 mm x 1.25 mm (0.417kg/mtr) thick , interlocking section of size 40 mm x 18 mm x 1.10 mm (0.469kg/mtr) thick and handle section of size 40mm x 18 mm x 1.25 mm (0.417kg/mtr) thick including providing and fixing 304 grade stainless steel mosquito proof mesh in the shutter using approved quality minimum two nos.PVC rollers, necessary locks, handles and other required fittings, making shutter removable as and when require etc. complete as directed by Engineer in charge.(Note: All aluminium sections and fitting are 15 micron anodized/ powder coated).	2.00	m2

43	Providing, making and fixing fully glazed aluminium partition/ fixed glazing using 63mm x 38mm x 1.65mm (not less than 0.942kg/mtr) 15 micron / powder coated anodized aluminium single groove partition section and 63mm x 38mm x 1.53mm (not less than 0.942kg/mtr) 15 micron / powder coated anodized aluminium double groove partition section for frame, providing and fixing 5mm thick clear plain glass fixed with glazing clips, rubber gasket etc. complete.	13.00	m2
44	Providing and fixing of Single glazed modular Profile Partition System VENUS-45 or IITB approved make with 10mm thick toughened glass with a tested sound reduction Value from 28 TO 32 Db Wide Line single glazed partition with 10mm thick toughened glass. The panels are supported by Aluminium section of 45*25*1.2mm fixed to RCC slab with spacing as manufacturer specification. All sections shall be duly anodised up to 15-16 microns with 6063-T5 grade and required accessories ie glass to glass aluminium I sections, T section & 90 degree sections & Glass packing to adjust the floor level. Ceiling profile, Floor profile and wall profile are 25 mm visible face and 100 mm wide with 10mm toughen glass & insertion of Thermoplastic gasket to adhere the airtight as per manufacturer specification. including all necessary Hardware etc. Complete.	9.00	m2
45	Providing & fixing ISI approve long swan neck pillar tap jaquar make including necessary fixtures etc. complete as directed	1	No
46	Providing and fixing oval shape white earthenware below counter wash hand basin of Parryware make including one cold water angle cock of Jaguar make (Continental series), click clack waste coupling, Bottle trap etc. complete as directed.	1	Nos
47	Providing, fabricating and fixing openable shutter below platform using aluminium anodized finish 68X22 mm aluminium shutter profile section for L-handle (Top member) and 45X22 mm aluminium profile shutter section for vertical and bottom members. providing and fixing 4mm thick one side designer or colour aluminium composite sheet inside shutter, L-corners patti for fixing shutter in right angle, also including 2 nos soft closing hinges for each shutters, L-pipe section for required location and other required fittings and fixtures etc. will be complete as directed (fittings and fixture approved by Engineer In-charge before fixing)	9.00	m2
48	Constructing chambers of internal clear dimensions 900mm x 600mm with 230mm thick brick masonry wall in cement mortar 1:6 over abed of 150mm thick cement concrete M-20 (1:1½:3) foundation with 150mm minimum offset beyond masonry wall plastering with cement mortar 1:4, 12mm thick on internal, external and all exposed faces, finished with floating coat of neat cement including providing and fixing precast R.C.C. frame and cover of suitable size, medium duty (weight carrying capacity of 300 Kg/m2), manufactured by KK Industries or equivalent as approved by Engineer Incharge and fixing with cement concrete coping M-20 (1:1½ :3) and plastering complete including necessary dewatering, if required etc. for chambers of depth upto 1000mm.	1	Nos
49	Providing and fixing Class C G.I. Pipes 15 mm dia nominal bore complete with G.I. fittings and clamps, making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall etc. completed as directed.	5.00	Rmt
50	Providing and fixing Class C G.I. Pipes 20 mm dia nominal bore complete with G.I. fittings and clamps, making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall etc. completed as directed.	5.00	rmt

51	Providing and laying 75mm dia. P.V.C. pipes conforming to I.S. in trenches including proper slope, filling the joints using rubber gasket with solvent cement etc. completed as directed.	5.00	Rmt
52	Providing and fixing in position best quality salt glazed stone ware gully trap with 150mm x 150mm square inlet and 100 mm n.b. outlet conforming to IS 651 including embedding the trap in M-15 (1:2:4) cement concrete, construction of brick masonry chamber 300mm x 300mm internal in 230mm thick brick masonry, plastering, finishing with neat cement floating coat, providing and fixing C. I. cover and frame weighing not less than 7 kg, etc including removing the old damaged gully trap, connecting all old and new inlets and out let pipes including running lines, jointing etc. all complete as directed.	1	Nos
53	Providing and fixing 100mm(ID) dia. ISI approved HDPE pipes manufactured by ARHAM Engineering/ BERLIA /NOCIL / PIL with wall thickness of 6 mm to 8mm for taking sewage waste water with all required fittings such as bend, elbows etc. with proper line and gradient connecting all joints with fusion butt welding by using suitable welding machine or hot plate, testing the line & joint as per manufacturer specification etc. all complete as directed by Engineer In-charge.	5.00	Rmt
54	Providing and fixing 150 mm inner diameter ISI approved HDPE pipes manufactured by ARHAM Engineering/ BERLIA /NOCIL / PIL with wall thickness from 10mm to 14mm for drainage pipe line with all required fittings etc. with proper line and gradient connecting all joints with fusion butt welding by using suitable welding machine or hot plate etc, testing the line & joints with smoke test method as per manufacturer specification or as per direction of Engineer In-charge etc. all complete as directed.	5.00	Rmt
55	Providing & laying brickbat coba on terrace, chajjas & in w.c. and bath in all positions in cement mortar 1:5 with waterproofing compound at the rate of 2% by weight of cement and covering 10 years' guarantee including all leads, lifts including furnishing a guarantee on requisite judicial stamp paper etc. complete.	1.00	m3
56	Providing and applying exterior coating for wall including Cleaning the surface, removing the laitance, greese, old paints, contaminants, curing compound with wire brushing with water pressure wash. Fine hair line cracks more than 0.50 mm must be widened up to 5 mm minimum in V shape and then fill cracks with Dr. Fixit Crack-X Paste on masonry plaster surface. Apply primer coat prepared with Dr. Fixit Crack-X Paste and water in 1:1 proportion over the crack. Fill Dr. Fixit Crack-X Paste when the surface is tacky and not dried completely. Press Dr. Fixit Crack-X Paste firmly into the crack with a spatula or putty knives and level with the surface. Care must be taken to avoid formation of cavities or bubbles during application. Allow it to set for 24 hours and then apply another coat of Dr. Fixit Crack-X Paste. Apply one coat of Dr. Fixit Primeseal with water in proportion of 2:1 and stir well until a uniform consistency is achieved. Apply a single coat of diluted Primeseal on the cleaned substrate. Allow it to dry for 2 to 3 hours. Apply Base coat of undiluted Dr. Fixit Raincoat Waterproof Coating over the primed surface. Allow the Dr. Fixit Raincoat Waterproof Coating to dry for 4 – 6 Hrs of approved colour. Apply using brush / roller / airless spray. Apply top coat of undiluted High Build durable exterior waterproof wall coating Dr. Fixit Raincoat Select Top coat over the Dr. Fixit Raincoat Waterproof Coating at applied areas of approved colour.	644.00	m2

	Apply using brush / roller / airless spray to achieve DFT of 170 – 180 microns. Allow the Dr. Fixit Raincoat Select Top coat to dry for 6 – 8 Hrs. Allow the coated surface to air cure fully for 7 days. Work includes scaffolding and covering the floor, window glass with plastic sheet and as directed by this office. Work Shall be got executed through certified applicator of the product manufacturing company only and work shall be guaranteed for 03 years by the contractor on requisite stamp paper including submitting written guarantee from said certified applicator. Contractor to submit re-counsillation statement along with challans for work done		
57	Providing and applying three coats of Dr. Fixit Roof seal coating including preparing surface by pressure washing the surface to remove all algae, mould, dirt, dust, chalking and waste products. All visible hairline cracks more than 0.50mm and not giving hollow sound on the IPS/screed or at the junctions of flat roof & vertical parapet wall, pipe joints, should be cut and widen V shape with mechanical cutter in the size (6mm W x 6mm D) and fill with Dr. Fixit PU Sealant covering the entire area uniformly with suitable gun. Allow sealant to cure a minimum 24 hours. Apply minimum 50mm - 100 mm width 45 GSM Glass Fibre Mesh / non-woven geo textile fleece with the coat of Dr. Fixit Roofseal Select along the length of crack. Apply one coat of Dr. Fixit Primeseal primer dilute with water in the ratio 2:1. Allow it to dry for 2 to 3 hours. Apply 1st coat of Dr. Fixit Roofseal Select at the rate of 2.0 sqmt / litre / coat. An open 45 Gsm glass fibre mesh of 2.5 mm x 2.5 mm must be sandwiched between the first and second coat. While the 1st coat is still wet, place the fibre mesh on it.	3.00	m2
	Allow the first coat to dry for 6-8 hours. Apply second coat of Dr. Fixit Roofseal Select with the same application coverage. Application direction of second coat should be perpendicular to that of the first coat. Allow second coat to dry for 6-8 hours. Apply third coat of Dr. Fixit Roofseal Select at an application direction that is perpendicular to that of the second coat with same application coverage rate. Check to see no void surface is left untreated / uncoated. Allow the system to air cure for 7 days minimum. A total thickness of 1 mm must be achieved when Dr. Fixit Roofseal Select is dry. Work Shall be got executed through certified applicator of the product manufacturing company only and work shall be guaranteed for 03 years by the contractor on requisite stamp paper including submitting written guarantee from said certified applicator. Contractor to submit re-counsillation statement along with challans for work done.		
58	Providing and laying waterproofing treatment of 120mm av. thickness consisting of 12mm thick layer in cement mortar 1:3 with water proofing compound 2% by weight of cement as base, constructing and laying brick bat coba in cement mortar 1:5 with waterproofing compound at the rate of 2% by weight of cement and having average thickness of 80mm and finishing with 20mm thick cement plaster layer in cement mortar 1:3 with water proofing compound 2% by weight of cement including laying glass fibre cloth of approved quality in top layer including all lead, lifts and laid to proper slope to drain off water entirely including watta at the junction of parapet and work upto a height of 300mm or as directed and including finishing the top layer of water proofing treatment with false marking of 30cm x 30cm or as directed and covering the whole treatment with seven years' guarantee, on requisite stamp paper etc. complete.	107.00	m2

59	Providing and laying water proofing cement concrete flooring to terrace to average 50mm thick with 1:2:3 cement concrete laid to proper level and slope using silt free clear river sand including compaction, filling joints, adding recommended waterproofing admixtures @ 2% by weight of cement, marking lines to give appearances of tiles of 30cm x 30cm or other approved size laid diagonally / square, finishing with extra cement in any colour as directed, testing the roof by ponding with water for 14 days, providing waterproofing guarantee for 3 (three) years in requisite non judicial stamp paper in favour of IITB including all lead and lift etc. complete.	54.00	m2
60	Fixing temporary partition during execution of work at site made up of plywood/ GI sheet including vertical support of props/teakwood/ plywood, transportation, lead, lift, removing the partition after completion of work etc. completed as directed.	80.00	m2
61	Providing and fixing reflective type sun control film of approved type of Garware make with cutting, fixing etc. complete as directed.	30.00	m2
62	Providing and fixing blackout horizontal (Marvell Make) roller blinds water resistant cloth of required size and colour including all necessary accessories and installation at any height etc.complete all as directed. (sample of blind should be approved before installation)	24.00	m2
63	Providing and fixing signboards with 3mm thick ACP sheet & radium sticker background including pasting, computerized designing & radium sticker cutting and pasting, fixing etc. all complete as directed by Engineer in charge.	4.00	m2
64	Providing and fixing in position Three track aluminium Domal Sliding window using sections of 101.5mm x 50mm for bottom, sides and top. (not less than 1.798 kg/mtr) The shutter should be of Handle Interlocking, bearing bottom of size 27 x 65 mm (not less than 0.91 kg/mtr) Domal Clip (not less than 0.41 kg/mtr) , including providing and fixing 5 mm thk. glass in the shutter using rubber gasket, approved quality minimum two nos. PVC rollers for each shutter, necessary locks, handles, PVC lining and other required fittings, etc. complete as directed by Engineer in charge.(Note: All aluminium sections 15 micron anodized/ powder coated).	13.00	m2
65	Providing and fixing in position Two track aluminium Sliding window using Domal sections of 66.5mm x 50mm for bottom, sides and top. (not less than 1.329 kg/mtr) The shutter should be of Handle Interlocking, bearing bottom of size 27 x 65 mm (not less than 0.91 kg/mtr) Domal Clip (not less than 0.41 kg/mtr) , including providing and fixing 5mm thk.glass in the shutter using rubber gasket, approved quality minimum two nos. PVC rollers for each shutter, necessary locks, handles, PVC lining and other required fittings, etc. complete as directed by Engineer in charge.(Note: All aluminium sections 15 micron anodized/ powder coated).	13.00	m2
66	Providing and applying acrylic synthetic plaster (Dura plaster) of IITB approved make manufacturer over existing cement plaster or concrete surface including removing existing paint/synthetic plaster to receive the acrylic synthetic plaster as per manufacturer specification Including all the necessary tools & plants,stepladder etc, complete all as directed by Engineer in charge.	644.00	m2
67	Providing and fixing 3mm thick exterior grade ACP sheet of approved colour and pattern over exisitng aluminium frame, fixing the panels using 3M tape, filling the joints using 789 grade silicon sealant with all required fittings and fixtures, screws, hardware using scaffolding or any mechanical arrangements erected for ACP facade cleaning work etc complete as directed by Engineer In-charge. .	27.00	m2

68	Providing & Fixing of G.I Lay-in perforated or plain metal ceiling system consisting of 600x600mm size grid with fleece laying in tiles of pre-coated galvanized steel in 0.4/0.5 mm thickness in required colour with 15mm wide T - section silhouete flanges of required colour having rotary stitching on the main Runner including P/F 1200mm & 600mm cross Tees as per manufacturer specifications and Engineer-in-Charge.	145.00	m2
----	---	--------	----

1) Note : This schedule of work is given for reference purpose only. Contractors are requested to quote your rates online in financial bid.

2) If you will engage labourer 20 or more any day, you have to get labour licence as per contract Regulation & Abolition Act 1970 Rule 1971, and also, you have to keep all such record for inspection to the Principal Employer. If you will engage labour up to 10 Nos. per day, you have to file returns after completion of work as per Building & Construction Act to the Office of Regional Labour Commissioner (Central), Sion, Mumbai.

3) This work is to be executed as per the the clauses mentioned in the tender document signed by you. In addition to the existing safety clause of the tender document a penalty of Rs.5,000/- per case will be recovered from the bills of the particular works, in case any such safety violations are noticed.

4) 01% amount will be deducted from the bills for safety related measures which will be reimburse along with the final bill.

5) Taxes as per government notification time to time.

6) Contractor must pay GST Taxes to concern authority within 30 days time limit after receipt of payment from IIT Bombay & said record must be submitted to IIT Bombay Accounts Section, otherwise action will be taken as deemed fit.

7) If any malpractices / fraud / negligent professional behaviour or any discrepancy / inconsistency / disparity / deviation / disagreement / dissimilarity / mismatch noticed, their contract will be terminated by issuing one month notice by following legal procedure and will be blacklisted and informed to all Government Authorities and Organisations.

6 
22/6/26
Superintending Engineer (I/C)
Dik 19/6 Juc 22/6