



INDIAN INSTITUTE OF TECHNOLOGY BOMBAY
ESTATE OFFICE
NOTICE INVITING TENDER

Telephone No. 022 2576-4060,022-2159-6922 email id drestate@iitb.ac.in

IIT Bombay invites digitally signed Technical Bid & Financial Bid for following work from the contractors having **similar** experience in Central Government Departments / State Government Departments / Central or State Autonomous Bodies / State or Central Public Sector Undertakings & Large Private Organizations. The detail of work is given below:

Sr. No.	Name of Work	Estimated Cost (In Rs.)	EMD (Rs.)	RFX	Duration of contract
1	Construction of Fire escape MS Staircase in the Mechanical Department EO/A/ACAD/WKS-85/26-27	Rs 26,63,067/- Incl.18% GST	Rs.53,000/-	6100003088	06 months excl. monsoon

Intending bidders need to register themselves on the IIT Bombay portal i.e. <https://portal.iitb.ac.in/vrp/index.jsp> to get User ID and Password. Please visit https://portal.iitb.ac.in/vrp/vrp_srm_docs.jsp for configuration process and user manual. For queries regarding vendor registration, and configuration process please contact on 022 - 2159 3001 (MDM Help-desk).

All tender documents, forms, etc are available online on <https://www.iitb.ac.in/resources/vendors-tenders> and Central Public Procurement Portal (CPPP) e-tender publishing portal of the Government of India.

Date and time of uploading of tender documents are from 14.08.2026 to 28.08.2026 till 11:15 a.m. Date of opening of Technical Bid will be 28.08.2026 at 11.30 a.m. and Financial Bid 02.09.2026 (Tentative).

All contractors/agencies should submit technical bid with the following documents, failing to which their tender will be summarily rejected from the tendering process:

1) i. Experience of having successfully completed works during the last 7 years ending last day of the month previous to the one in which applications are invited :

Three similar completed works costing not less than the amount equal to **40%** of estimated cost put to tender,

OR

Two similar completed works, costing not less than the amount equal to **50%** of the estimated cost put to tender

Or

One similar completed work of aggregate cost not less than the amount equal to **80%** of the estimated cost.

ii. One completed work of any nature (either part of (i) or a separate one) costing not less than the amount equal to **40%** of the estimated cost put to tender with some Central Government Departments / State Government Departments / State or Central Autonomous Bodies / State or Central Public Sector undertakings.

2) Upload a copy of the information in respect of manpower/mandays for above said work must be given in undertaking with official signature and seal/stamp, otherwise tender will be rejected.

3) P. F. registration certificate.

4) P. F. challans of last 12months.

5) ESIC registration certificate and copies of ESIC challans of the last 12 months (as per the labourers engaged during a particular month). Contractor name should be mentioned in the challans else the agency will be disqualified. OR Contractors' all risks insurance (CAR policy)

6) PAN card.

7) GST registration certificate.

8) Income Tax Return for **assessment year** i.e. of **2023-24 ,2024-25 & 2025-26.**

9) List of Equipment's, Machinery, Tools.

10) List of Technical Staff with copies of their Degree/diploma certificate.

11) **Submit** DD/FDR/BG of Rs. 53,000/- in the name of "The Registrar, IIT Bombay" **before the opening of Technical Bid.** Contractors are also requested to upload a scanned copy of it to the online Tendering portal.

12) Power of Attorney, if any.

13) Proof of Constitution: An affidavit in case of Sole Proprietorship, Partnership Deed in case of Partnership Firm, Article of Association in case of Private / Public Limited Companies.

14) **Litigation history** of the agency is required to be upload along with the application. A tender would not be awarded if any inquiry proceeding / criminal case is found pending against the agency. If there is no enquiry then undertaking has to be uploaded in the format given.

15) Bank Solvency certificate 40% of estimated amount issued within one year from any Nationalized / Schedule Bank from the date of publishing of Tender.

16) Detail statement for work completed, work in hand including balance commitment of work should be enclosed for last three year commencing from 1st April and ended with 31st March and contractor should upload his details as per **Annexure'A'** format with support of xerox copies of work order and work completion certificates, otherwise the bid capacity will not be calculated and his technical bid will be summarily rejected.

Terms & Conditions :

The documents listed below from Sr. No. 1 to 16 is mandatory for qualification in the technical bid evaluation process.

Select 'N5' tax code for 18% GST and upload all the above mentioned documents in "C folder" of online SRM tendering portal.

The work will be executed with lowest bidder as per the terms and conditions of work order and tender documents signed by the lowest bidder.

The validity of the bids will be valid for 6 months from the date of opening of tender.

No work will be subletted to third party. If found payment of final bill will not be processed and the contractor's name will be removed from the enlistment without giving him further notice.

The rates are prepared from CPWD DSR 2023 & Rate Analysis.

Contractors are strictly prohibited from engaging in any correspondence related to tender documents with anyone other than the Tender Section. Any violation will result in disqualification from all future tenders.

No queries will be entertained within 24 hours prior to the opening of the tender. We kindly request all contractors to upload their quotations well in advance of the submission deadline to ensure a smooth and timely process.

IIT Bombay reserve its rights to reject any or all tenders without assigning any reason and without any reference. IIT Bombay reserves the right to request a detailed justification of the quoted rates from the lowest bidder, if deemed necessary by the Engineer-in-Charge. Should the justification provided by the bidder be considered unsatisfactory or unsubstantiated, the Engineer-in-Charge shall have full authority to reject the bid, irrespective of it being the lowest.

sd/-

Superintending Engineer (I/C)

DECLARATION

- (a) We are not involved in any litigation that may have an impact of affecting or compromising the works as required under this tender.
- (b) We are not black-listed by any Central/State Government/Public Sector Undertaking in India.
- (c) We hereby confirm and declare that M/s [Company Name] does not have any Litigation / Arbitration History with any Government department, Public Sector Undertaking (PSU), or Private Sector agency for works executed during the **last 5 years**.
- (d) I/we undertake that the documents submitted are genuine/authentic and nothing material has been concealed therefrom and that I/we are not debarred by any Government organization and are competent to have the contract. I/we understand that the contract is liable to be cancelled, if found to be having obtained, through fraudulent means/concealment of information.

(Signature of Authorized Signatory)

Name of the bidder: _____

Complete Address: _____

Address (Works), if _____

any: Contact Nos. _____

TO BE UPLOADED ON SRM TENDERING PORTAL WITH FINANCIAL BID

**ANNEXURE 'A' (FORMAT)
TECHNICAL BID**

File No. : EO/A/ACAD/WKS-85/26-27

Name of Work : Construction of Fire Escape MS Staircase in the Mechanical Department.

Name of the Contractor -----

Sr. No.	Name of Client	Name of Works	2022-23 (In Lakhs)	2023-2024 (In Lakhs)	2024-2025 (In Lakhs)	2025-2026 (In Lakhs)	
						Completed	Balance
			-	-	-	-	-
			-	-	-	-	-
Total Amount (In Lakhs)			-	-	-	-	-

Note : Contractor must submit his details as per Annexure 'A' with declaration stating that **he is possessing all the original copies of work orders and experience certificates, it will be produced as and when required to IIT Bombay.** However, if it is found false at later stage, the contractor will be debarred or blacklisted. Whereas, if information is not submitted as per Annexure 'A' format his bid capacity will not be calculated and his tender will be summarily rejected.

Superintending Engineer (I/C)

Signature of Contractor
Name & Address in full

WORKS UNDERTAKING

EO/A/ACAD/WKS-85/26-27

To,
Superintending Engineer (I/C)
Indian Institute of Technology,
Powai, Mumbai – 400 076.

Sub : Construction of Fire Escape MS Staircase in the Mechanical Department.

Dear Sir,

We are hereby quoting all the rates for the attached schedule of short tender of the above mentioned job.

We hereby accept & signed all the General Terms and Conditions and special Conditions of Contract.

The work will be completed within specified time limit of Six months (Excluding monsoon) as mentioned in the notice inviting for short tenders.

The following information is required to be provided.

I / We agree to keep the tender open for One Hundred and Eighty (180) days from the due date of its opening / One Hundred and Eighty days from the date of opening of financial bid in case tenders are invited on 2/3 envelope system and not to make any modification in its terms and conditions.

	Male	Female
No. of Unskilled casual labour to be required per day.		
No. of Skilled casual labour to be required per day.		
Total Mandays required for completion of work.		

Thanking you,

Yours faithfully,

Signature of the Contractor
With official Seal / Stamp of the firm

INDIAN INSTITUTE OF TECHNOLOGY, BOMBAY
POWAI, MUMBAI-76

EO/A/ACAD/WKS-85/26-27

ESTATE OFFICE

Name of Work :- Construction of Fire Escape MS Staircase in the Mechanical Department.

Sr. No.	Description of work	Qty	Unit
1	Excavation for foundation, trenches, Roadway etc. in earth, soil of all types, sand, gravel, soft and hard murum, soft rock etc. including removing the excavated materials up to a distance of 50 meters beyond the site of work and lift up to 1.50 meters, stacking and spreading as directed preparing the bed for the foundation and necessary dewatering using pump, backfilling, ramming, watering, including shoring and strutting, providing necessary barricading around excavated area etc. complete.	12.00	Cum
2	Dismantling plain cement concrete work including breaking concrete by chiselling, wedging etc., and stacking the debris upto a distance of 50 metres or spreading as directed.	8.00	Cum
3	Carefully removing internal or external plaster in patches or any length without damaging structure brickwork in the vicinity by using electric cutting tools including cutting a groove first to demarcate exact area of damage taken place stacking the debris with in 50 meter, cleaning the site etc. complete. including covering the furniture, floor, windows and partitions with plastic sheets while chipping etc. including working platform / stepladder completed as directed. Note:- a) No extra payment shall be made for extra thickness removed. b) Proper tools to be used for removal of concrete and it should be seen by contractor no damage on the other side / near by area will be taken place and if required other portions are to be checked by the contractors with respect to the damage before commencement of the work. c) The area in vertical plane shall be measured.	100.00	Sqm
4	Chipping of unsound/weak concrete material from slabs, beams, columns etc. with manual Chisel and/ or by standard power driven percussion type or of approved make including tapering of all edges, making square shoulders of cavities including cleaning the exposed concrete surface and reinforcement with wire brushes etc. and disposal of debris for all lead and lifts, including working platform / stepladder all complete as per direction of Engineer-In-Charge	100.00	Sqm
5	Cleaning of reinforcement from rust from the reinforcing bars to give it a total rust free steel surface by using alkaline chemical rust remover of approved make with paint brush and removing loose particles after 24 hours of its application with wire brush and thoroughly washing with water and allowing it to dry, including working platform / stepladder all complete as per direction of Engineer-In-Charge	100.00	Sqm
6	Providing, mixing and applying bonding coat of approved adhesive on chipped portion of RCC as per specifications and direction of Engineer-In-charge complete in all respect. SBR Polymer (@10% of cement weight) modified cementitious bond coat @ 2.2 kg cement per sqm of surface area mixed with specified proportion of approved polymer. including working platform / stepladder etc. Note: The actual consumption of polymer shall be measured for payment on Sqm basis. Challans of authorized dealer will be verified.	500.00	Sqm
7	Providing and Placing in position readymix polymer mortar manufacture by Dr. Fixit, Sunanda, Roff, MC Bouchmey, Chembond and adding water in the proportion of 1:0.14 (polymer mortar : water) in prepared grooves / cracks of the concrete court in layers as directed including mixing the polymer mortar with water using forced action mixer mild curing with water for 3 days and finishing the surface in all respect. including working platform / stepladder etc. Complete as directed. (Payment will be paid for the actual quantity of polymer mortar used on weight basis. Challans of authorised Dealer will be verified etc all complete as directed by Estate office).	5,000.00	Kg

8	Providing and laying super fluid micro concrete of approved manufacturer at any floor after reinforcement treatment coat including providing marine plywood formwork in line and level, sealing the joints/ gaps with POP & cleaning, curing etc. complete. (Payment will be paid for the actual quantity of polymer mortar used on weight basis. including working platform / stepladder etc. Challans of authorised Dealer will be verified etc all complete as directed by Estate office).	1,000.00	Kg
9	Laying dry trap / rubble stone soling of required thickness including hand packing and compacting in proper level all complete as directed by Engineer-in-charge.	14.00	Cum
10	Providing and laying cement concrete 1:11/2: 3 (M-20) plinth level to upto any floor using sand as fine aggregate and graded stone aggregate 20mm maximum size for foundation, coping and bedding, levelling, dewatering by any means, compaction, finishing, curing etc. complete all as directed.	10.00	Cum
11	Providing and laying in position ready-mixed or machine batched or machine mixed design mix M-30 (1:0.75:1.5) grade cement concrete (with minimum cement content 350Kg/Cum) for all work up to plinth level for reinforced cement concrete work, including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement, including admixtures in recommended proportions as per relevant IS code to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge including compacting, roughening the surface if special finish is to be provided, casting cubes and testing etc. completed as directed.	2.50	Cum
12	Centering and shuttering including strutting, propping etc. and removal of form for all heights :Lintels, beams, plinth beams, girders, bressumers and cantilevers	20.00	Sqm
13	Centering and shuttering including strutting, propping etc. and removal of form for all heights: Columns,pillars,piers,abutments,posts nad struts	15.00	Sqm
14	Providing and fixing in position tor steel bar having grade Fe-500D or more for reinforcement of various diameters for R.C.C. footings, foundations, slabs, beams, columns, canopies, staircases, chajjas, lintels, pardies, coping, fins, dowel bars with sleeve, tie bar, any other required work etc. as per detailed designs, drawings and schedules including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required completed as directed.	800.00	Kg
15	Providing and fabricating structural steel works in rolled sections like joists, channels, angles, tees, hollow sections and any other required sections etc. as per detailed designs & drawings for supports, rafters, purlins, railing, staircase and any other work including fixing in position with connecting plates, braces and welding, riveting, bolting as necessary including one coat of redoxide priming coat etc. complete as directed.	2,000.00	Kg
16	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.In stringers, treads, landings etc. of stair cases, including use of chequered plate wherever required, all complete	800.00	Kg
17	Providing and applying two coats of synthetic enamel paint of IITB approved brand and shade to wood and steel work Scrapping, cleaning, covering the floor, windows, instruments during painting etc. complete.	50.00	Sqm

18	Providing sand face plaster externally using approved screened sand in all positions including base coat of 15mm thick in cement mortar 1:4 using water proofing compound per cement bag as per manufacturer specification and curing the same for not less than two days and keeping the surface of base coat rough to receive the sand faced treatment not to exceed 8mm thick in cement mortar 1:4 using water proofing compound per cement bag as per manufacturer specification as per manufacturer specification, finishing the surface by taking out grains and curing for 14 days. including working platform / stepladder etc. completed as directed.	100.00	Sqm
19	Providing internal cement plaster 20mm thick in a single coat in cement mortar 1:4 without neeru finish to concrete or brick surfaces in all positions including curing, working platform / stepladder etc. completed as directed.	20.00	Sqm
20	Providing second class burnt brick masonry with IS approved quality well burnt bricks having crushing strength of 35 kg. / square cm. and maximum water absorption of 20% in cement mortar 1:6 in superstructure including striking joints, racking out joints, watering etc. complete as directed.	10.00	Cum
21	Providing and fixing not less than 16-18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut Granite (area of slab above 0.50 m2) for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.	10.00	Sqm
22	Providing and erecting at site steel tubular H – frame double scaffolding with bracings to all heights as directed by engineer in charge before commencement of work and removing the same after completion of all external work requiring double scaffolding.	200.00	Sqm
23	Providing and filling separation crack of 75mm width and 25mm deep with polymer modified cementitious mortar. a) Filling polymer modified cementitious mortar in layers of 20mm thick (applying bond coat at every layer) upto profile of concrete in vicinity (composition of mortar: cement 1Kg.: polymer (SBR) of approved manufacturer 15% by wt. of cement : 3Kg silica sand (grading IS 383, zone II, silt content = 0%) over a polymer + cement bond coat including applying making tape on both side of groove, cleaning, finishing to match the plaster in vicinity, disposing of debris anywhere in IITB campus, cleaning as directed etc. complete. b) Proportion c) Bond coat d) SBR polymer + cement in the ratio 1:1 by volume e) Polymer modified cementitious mortar f) SBR polymer 150ml. g) Cement 1 Kg. h) Silica sand 3.0 kg. (Note: - Demarcating groove, breaking Plaster / concrete shall be paid under respective items).	100.00	Rmt
24	Cutting, demarcating grooves at any height with electrically operated cutter machine between sound and unsound plaster, cracks on external wall, separation cracks etc. complete.	100.00	Rmt
25	Providing and applying HILTY HIT-HY RE 500 injection in RCC including fixing in steel diameter 8mm to 12mm & length 4" to 6" reinforce bars including drilling hole as per manufacturer specifications, blowing out the hole and finishing etc. Complete as directed.	5.00	Nos
26	Providing uncoursed rubble masonry of trap stones in cement mortar 1:6 (Cement:sand/grit) including racking out joints when plastering is to be done, striking out joints, watering and pointing with cement mortar 1:3 on outside exposed faces, including providing M-20 grade concrete block header @ 1 header per sqm. to the full thickness of wall, providing weep holes with 100mm dia P.V.C pipes etc. all complete as directed.	15.00	Cum

27	Providing and fixing light duty ductile iron grating of size 450mmx600mm of NECO or IITB approved make in proper line and level all complete as directed.	80.00	Nos
28	Providing and fixing multicell 16mm thick (min.) Polycarbonate UV Insulated sheets of Coxwell/ Danpal/ Palram/ DPI Daylighting/sabic/tuflite make of approved colour in curve or plane shape, panel width 900mm (min.), panels shall be uniform in colour with multi-cell structure. Weight of the panel shall not be less than 3.31Kg/sqm. Panels shall have vertical standing seam at both sides of the panel including all fittings and fixtures such as snap on connector with grip lock 1 / 2 tooth locking mechanism for water and air tightness. Panels shall be fixed on purlins with SS expansion fastener and polycarbonate U connectors. Panels shall be sealed with additional End-cap/Aluminium U profile(mill finish) for ends or welded ends. Panels shall be fixed on end wall by making grooves on wall plaster and fixing the sheet with necessary cement plastering/ grouting with required flashing at the junction of wall/concrete surface and sheets and other required fittings as per manufacturer specifications etc. Panels should be covered under 10 years warranty against any manufacturing defects Note: Payment for flashing will be made in separate item.	20.00	Sqm
29	Providing and applying exterior coating for wall including mechanical cleaning of the external surface and treating surface in sound, clean and free from dirt, oil and other loose material and may be done with vacuum cleaning if required. All surface cracks upto 5 mm width will be filled up with Dr. Fixit Crack X paste or similar material. The external surface will be primed with Dr. Fixit Primeseal (or equivalent BASF/ FOSROC/ STP) diluted with potable water in the ratio of 2:1 by volume prior to application of Dr. Fixit Raincoat. Allow it to dry for at least 2 to 3 hours and then apply Dr. Fixit Raincoat or equivalent (BASF/ FOSROC/ STP) having DFT of 110 micron, elongation of > 100% as per ASTM D412-02 and algae Fungal resistance as per SS 345-1998. Accelerated weathering (2000 Hrs UV Exposure) as per ASTM D4587 No defects) in 2 coats by brush, roller or spray with an interval of 5 to 6hrs. Allow it to air cure for 7 days and do not dilute Dr. Fixit Raincoat by any means. cleaning the surface thoroughly, watering the surface etc. complete including covering the floor, window glass with plastic sheet and as directed by this office. Work Shall be got executed through certified applicator of the product manufacturing company only and work shall be guaranteed for 3 years by the contractor on requisite stamp paper including submitting written guarantee from said certified applicator.	450.00	Sqm.
30	Disposing debris, loose stones, boulders, concrete pieces broken etc. collected and stacked as directed including loading in trucks, transporting out of IIT Campus including obtaining approval from Government/ private land owners for disposing off on to their approved location. The contractor will be solely responsible for disposing debris out of campus and the debris are to be removed from site within 72 hours from stacking (30% voids will be deducted from actual measurement for debris, loose stones, boulders, concrete pieces).	6.00	Cum
31	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil in IITB campus in low lying area as directed by Engineer In-charge. 30% voids will be deducted in case of truck measurement..All kinds of soil.	1.00	Cum
32	Providing and applying one coat of Berger Protectomastic self priming high build coating, solvent borne zinc rich primer, having thickness as per manufacturer specification including preparing the surface by thoroughly removing grease, oil and other containments preferably by using Bison degreasing solvent, using mechanical tools along with manual chipping and wire brushing to remove loose rust, thoroughly dust down all surfaces, followed by one coat of Epilux - 4 High Build Epoxy finish having thickness as per manufacturer specification followed by two coats of acrylic polyurethane enamel paint of Bergerthane finish of Berger having thickness as per manufacturer specification including tools, taking all safety measures etc complete..	200.00	Sqm

33	Providing, making and fixing fully glazed aluminium partition/ fixed glazing using 63mm x 38mm x 1.65mm (not less than 0.942kg/mtr) 15 micron / powder coated anodized aluminium single groove partition section and 63mm x 38mm x 1.53mm (not less than 0.942kg/mtr) 15 micron / powder coated anodized aluminium double groove partition section for frame, providing and fixing 5mm thick clear plain glass fixed with glazing clips, rubber gasket etc. complete.	10.00	Sqm
34	Providing, fabricating and fixing in position partly opaque and partly glazed aluminum anodized openable door in single or double leaf shutter using aluminum standard door section 80mm x 40mm (not less than 1.139kg/mtr) for verticals and middle, 100mm x 40mm (not less than 1.60kg/mtr) for top & bottom members, 4mm thick both side colour and designer aluminium composite sheet up to 1200mm height or as per plan and 5mm thick clear/ bajri glass above opaque panels, glazing clips, rubber gasket including using 3 nos stainless steel hinges 4" long for each shutter, 9" long stainless steel handles 2 nos. for each shutter, lock, stainless steel tower bolt 8" long 1 no for each shutter and other required fittings etc. all complete as directed. (All aluminium sections should be 15 micron anodized/ powder coated)	5.00	Sqm
35	Providing and applying one coat of acrylic primer and two coats of exterior acrylic paint of approved colour & shade of IITB approved manufacturer i.e. Berger, Asian, Killick Nixon, Goodlass, Nerolac, ICI, Decocem and as per manufacturer's specification on old or new plastered surface over concrete / brickwork, stonework as per manufacturer's specification including and cleaning the surface thoroughly with coir brush, watering the surface etc. complete including covering the floor, window glass with plastic sheet etc. all complete as directed by Engineer In-charge.	50.00	Sqm

1) Note : This schedule of work is given for reference purpose only. Contractors are requested to quote your rates online in financial bid.

2) If you will engage labourer 20 or more any day, you have to get labour licence as per contract Regulation & Abolition Act 1970 Rule 1971, and also, you have to keep all such record for inspection to the Principal Employer. If you will engage labour up to 10 Nos. per day, you have to file returns after completion of work as per Building & Construction Act to the Office of Regional Labour Commissioner (Central), Sion, Mumbai.

3) This work is to be executed as per the the clauses mentioned in the tender document signed by you. In addition to the existing safety clause of the tender document a penalty of Rs.5,000/- per case will be recovered from the bills of the particular works, in case any such safety violations are noticed.

4) 01% amount will be deducted from the bills for safety related measures which will be reimburse along with the final bill.

5) Taxes as per government notification time to time.

6) Contractor must pay GST Taxes to concern authority within 30 days time limit after receipt of payment from IIT Bombay & said record must be submitted to IIT Bombay Accounts Section, otherwise action will be taken as deemed fit.

7) If any malpractices / fraud / negligent professional behaviour or any discrepancy / inconsistency / disparity / deviation / disagreement / dissimilarity / mismatch noticed, their contract will be terminated by issuing one month notice by following legal procedure and will be blacklisted and informed to all Government Authorities and Organisations.

Superintending Engineer (I/C)

[Signature]
16/07/2016
15/7/2016
16/7