INDIAN INSTITUTE OF TECHNOLOGY BOMBAY
ESTATE OFFICE
NOTICE INVITING TENDER

Telephone No. 022 2576-4995,022-2159-6922 email id drestate@iitb.ac.in

IIT Bombay invites signed Technical Bid & Financial Bid for the following work from the contractors having similar experience in Central Government Departments / State Government Departments / Central or State Autonomous Bodies / Central or State Public Sector Undertakings / in reputed Private Companies. The detail of work is given below:

Sr. No.	Name of Work	Estimated Cost (In Rs.)	EMD (Rs.)	Mode of Tender	Duration of contract
1	Term contract for internal painting in various residing / vacant quarters at Hillside area. **EO/A/HILLSIDE/WKS-136/26-27**	Rs 74,65,739/- Incl.18% GST	Rs.1,49,000/-	**Item rate offline mode**	**12 MONTHS**

Intending bidders need to register themselves on the IIT Bombay portal i.e. https://portal.iitb.ac.in/vrp/index.jsp to get User ID and Password. Please visit https://portal.iitb.ac.in/vrp/vrp_srm_docs.jsp for configuration process and user manual. For queries regarding vendor registration, and configuration process please contact on 022 - 2159 3001 (MDM Help-desk).

All tender documents, forms, etc are available online on https://www.iitb.ac.in/resources/vendors-tenders and Central Public Procurement Portal (CPPP) e-tender publishing portal of the Government of India.

Date of submission of technical and financial bids, in 2 separate envelopes is on 13.11.2026 from 09:15 a.m to 11:15 a.m. in the tender box at 1st floor, Conference room, Estate Office. **The date of opening the technical Bid will be 13.11.2026 at 11:30 a.m and the date of opening of financial bid is on 20.11.2026 (Tentative)**

Interested contractors/agencies are requested to submit Technical bid and Financial bid in the Tender Box of the Estate Office.All contractors/agencies should submit technical bid with the following documents, failing to which their tender will be summarily rejected from the tendering process:

1) **i.** Experience of having successfully completed works during the last 7 years ending last day of the month previous to the one in which applications are invited :

Three similar completed works costing not less than the amount equal to **40%** of estimated cost put to tender,
OR
Two similar completed works, costing not less than the amount equal to **50%** of the estimated cost put to tender
Or
One similar completed work of aggregate cost not less than the amount equal to **80%** of the estimated cost.

ii. One completed work of any nature (either part of (i) or a separate one) costing not less than the amount equal to **40%** of the estimated cost put to tender with some Central Government Departments / State Government Departments / State or Central Autonomous Bodies / State or Central Public Sector undertakings.

2) Submit a copy of the information in respect of manpower/mandays for above said work must be given in undertaking with official signature and seal/stamp, otherwise tender will be rejected.

3) P. F. registration certificate.

4) P. F. challans of last 12months.

5) ESIC registration certificate and copies of ESIC challans of the last 12 months (as per the labourers engaged during a particular month).Contractor name should be mentioned in the challans else the agency will be disqualified.ORContractors' all risks insurance (CAR policy)

6) PAN card.

7) GST registration certificate.

8) Income Tax Return for **assessment year** i.e. of **2024-25 & 2025-26 & 2026-27.**

9) List of Equipment's, Machinery, Tools.

10) List of Technical Staff with copies of their Degree/diploma certificate.

11) Submit DD/FDR/BG of Rs. 1,49,000/- in the name of "The Registrar, IIT Bombay" in the Technical Bid Envelope.

12) Power of Attorney, if any.

13) Proof of Constitution: An affidavit in case of Sole Proprietorship, Partnership Deed in case of Partnership Firm, Article of Association in case of Private / Public Limited Companies.

14) **Litigation history** of the agency is required to be submitted along with the application. A tender would not be awarded if any inquiry proceeding / criminal case is found pending against the agency.If there is no enquiry then undertaking has to be submitted in the format given.

15) Bank Solvency certificate 40% of estimated amount issued within one year from any Nationalized / Schedule Bank from the date of publishing of Tender.

16) Detail statement for work completed, work in hand including balance commitment of work should be enclosed for last three year commencing from 1st April and ended with 31st March and contractor should submit his details as per **Annexure'A'** format with support of xerox copies of work order and work completion certificates, otherwise the bid capacity will not be calculated and his technical bid will be summarily rejected.

Terms & Conditions :

The documents listed above from Sr. No. 1 to 16 is mandatory for qualification in the technical bid evaluation process.

The work will be executed with lowest bidder as per the terms and conditions of work order and tender documents signed by the lowest bidder.

The validity of the bids will be valid for 6 months from the date of opening of tender.

No work will be subleted to third party. If found payment of final bill will not be processed and the contractor's name will removed from the enlistment without giving him further notice.

The rates is prepared from CPWD DSR 2023 & Rate analysis.

Contractors are strictly prohibited from engaging in any correspondence related to tender documents with anyone other than the Tender Section. Any violation will result in disqualification from all future tenders.

IIT Bombay reserve its rights to reject any or all tenders without assigning any reason and without any reference.IIT Bombay reserves the right to request a detailed justification of the quoted rates from the lowest bidder, if deemed necessary by the Engineer-in-Charge. Should the justification provided by the bidder be considered unsatisfactory or unsubstantiated, the Engineer-in-Charge shall have full authority to reject the bid, irrespective of it being the lowest.

Bids must be submitted between 09:15 a.m. and 11:15 a.m. on the tender opening date specified in the Notice Inviting Tender (NIT). Contractors are required to deposit their bids in the designated tender box located in the Conference Room on the first floor of the Estate Office.

The bid shall be submitted in a duly sealed envelope, clearly superscribed with the name of the work, work number, and type of bid enclosed (Technical Bid or Financial Bid) with company's name and signature on it. Envelopes secured with staples shall not be accepted, and bids submitted in such envelopes shall be rejected.

The Technical Bid shall include an index sheet, and all documents shall be properly numbered, arranged in the order specified in the index, and appropriately tagged with flags for easy identification and reference.

The contractor shall affix the company stamp and the authorized signatory's signature on each page of the bid documents. This requirement shall be strictly adhered to, particularly in respect of the Financial Bid.

sd/-
Dy. Superintending Engineer

DECLARATION

(a) We are not involved in any litigation that may have an impact of affecting or compromising the works as required under this tender.

(b) We are not black-listed by any Central/State Government/Pubic Sector Undertaking in India.

(c) We hereby confirm and declare that M/s [Company Name] does not have any Litigation / Arbitration History with any Government department, Public Sector Undertaking (PSU), or Private Sector agency for works executed during the **last 5 years.**

(d) I/we undertake that the documents submitted are genuine/authentic and nothing material has been concealed therefrom and that I/we are not debarred by any Government organization and are competent to have the contract. I/we understand that the contract is liable to be cancelled, if found to be having obtained, through fraudulent means/concealment of information.

(Signature of Authorized Signatory)

Name of the bidder: _____

Complete Address: _____

Address (Works), if any: Contact Nos. _____

TO BE UPLOADED ON SRM TENDERING PORTAL WITH FINANCIAL BID

ANNEXURE 'A' (FORMAT)
TECHNICAL BID

File No. : EO/A/HILLSIDE/WKS-136/26-27

Name of Work : Term Contract for Internal Painting in Various Residing/ Vacant Quarters at Hillside Area.

Name of the Contractor ----------

Sr. No.	Name of Client	Name of Works	2023-24 (In Lakhs)	2024-2025 (In Lakhs)	2025-2026 (In Lakhs)	2026-2027 (In Lakhs)	
						Completed	Balance
			-	-	-	-	-
			-	-	-	-	-
		Total Amount (In Lakhs)	-	-	-	-	-

Note : Contractor must submit his details as per Annexure 'A' with declaration stating that **he is possessing all the original copies of work orders and experience certificates, it will be produced as and when required to IIT Bombay.** However, if it is found false at later stage, the contractor will be debarred or blacklisted. Whereas, if information is not submitted as per Annexure 'A' format his bid capacity will not been calculated and his tender will be summarily rejected.

14/10/26

Dy. Superintending Engineer

14/10

14/10

Signature of Contractor
Name & Address in full

WORKS UNDERTAKING

EO/A/HILLSIDE/WKS-136/26-27

To,
Dy. Superintending Engineer
Indian Institute of Technology,
Powai, Mumbai – 400 076.

Sub : Term Contract for Internal Painting in Various Residing/ Vacant Quarters at Hillside Area.

Dear Sir,

We are hereby quoting all the rates for the attached schedule of short tender of the above mentioned job.

We hereby accept & signed all the General Terms and Conditions and special Conditions of Contract.

The work will be completed within specified time limit of One year as mentioned in the notice inviting for short tenders.

The following information is required to be provided.

I / We agree to keep the tender open for One Hundred and Eighty (180) days from the due date of its opening / One Hundred and Eighty days from the date of opening of financial bid in case tenders are invited on 2/3 envelope system and not to make any modification in its terms and conditions.

	Male	**Female**
No. of Unskilled casual labour to be required per day.		
No. of Skilled casual labour to be required per day.		
Total Mandays required for completion of work.		

Thanking you,

Yours faithfully,

Signature of the Contractor
With official Seal / Stamp of the firm

INDIAN INSTITUTE OF TECHNOLOGY BOMBAY

ESTATE OFFICE

EO/A/HILLSIDE/WKS-136/26-27

Name of Work :- Term Contract For Internal Painting In Various Residing/Vaccant Quarters At Hillside Area

Sr No.	Description/Schedule of work	Qty.	Rates in figure & words	Unit	Amount
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead as directed by Engineer Incharge	400.00		Sqm	
2	Exposing the existing damaged RCC members like columns, beams, slabs, chajjas, paradi, fins etc in patches or any length by using electrical cutting tools up to any depth till the corroded reinforcement will be opened allround without damaging brickwork, plaster in the vicinity, cleaning, stacking the debris with in 50 meters or spreading/leveling in low laying area as directed by Engineer Incharge, cleaning the site etc. complete, including covering the furniture with plastic sheet while exposing concrete. Note :- Proper tools to be used for removal of concrete. The exposed area shall be measured for the payment of this item. While exposing the ceiling area inside the quarter the existing tiles area shall be covered with shock absorbing material such rubbersheet or 12mm thick plywood sheet to resist the breaking of floor tiles.	150.00		Sqm	
3	Old reinforcement treatment providing and applying reinforcement treatment, comprising of following operations. Cleaning the reinforcement from all sides by using wire brush, tools etc. Application of rust converter such as Alkaline base(Rust kill A) as per manufacturers specification, cleaning as directed complete. Actual consumption of Alkaline base converter shall be measured for payment on weight basis. Invoice of authorized dealer will be verified. The chemical to be procured in sealed container & seal to be opened in presence of the IITB representatives.	30.00		Kg	

4	Providing and applying an effective bond coat of Polymer (SBR) Stuco latex of structural waterproofing (Cicco)/ Resicon 400, and cement in the proportion of 1:1 by using brush in multiples of coat as required to accommodate the whole thickness of PMM wherever required on the surface of old concrete / repaired concrete Polymer (SBR) of approved manufacturer should have the following properties: Suspended solid particles should not be less than 40%. Specific gravity should not be more than 1.01 PH should not be less than 8.5 Note: The actual consumption of bond coat shall be measured for payment on weight basis. Invoice of authorized dealer will be verified. The chemical to be procured in sealed container & seal to be opened in presence of the IITB representatives	150.00		Kg	
5	Providing and Placing in position readymix polymer mortar manufacture by Dr. Fixit, Sunanda, Roff, MC Bouchmey, Chembond and approved and adding water in the proportion of 1:0.14 (polymer mortar : water) in prepared grooves / cracks of the concrete court in layers as directed including mixing the polymer mortar with water using forced action mixer mild curing with water for 3 days etc. Complete. (Payment will be paid for the actual quantity of polymer mortar PX used on weight basis. Invoice of authorised Dealer will be verified etc all complete as directed by Estate office).	7500.00		Kg	
6	Providing and Placing in position Readymix Plaster manufactured by M/s. A. V. Conchem, Ultra-Tech Cement, Ready Plast, up to 20mm thick in one coat and adding water in the proportion of 1:0.17(Ready Mix Plaster : water) at any floor over the prepared Brick wall, Solid ,Hollow & AAC block work and Concrete RCC surfaces, as directed mixing the Readymix Plaster with water using forced action mixer including step ladder wherever required, mild curing will be done with water for 3-5 days etc complete. (Invoice of authorized dealer will be verified)	300.00		Sqm	
7	Providing and applying Birla wall care white cement based putty as per manufacturer's specifications in approved shade and colour to existing rough surfaces/ plaster surface/brick wall and ceiling as directed by Engineer in charge etc, complete	2650.00		Sqm	

8	Providing internal cement plaster for ceiling area upto 12mm thick in single coats in cement mortar 1:4 without neeru finish to concrete or brick surfaces in all positions with the use of step ladder and curing etc.all complete as directed by Engineer In-charge.	100.00		Sqm	
9	Providing and applying one coat of cement primer of approved manufacturer (Asian paints Decoprime wall primer or any other approved equivalent product of ICI or Goodlass Nerolac as directed by Engineer and as per manufacture specification including .Scrapping the old peeled off neeru finish /pop/ existing luster paint /concrete surface of ceiling /wall surface with sand paper and coating the surface with the use of step ladder etc, complete as directed.	24800.00		Sqm	
10	Providing and applying one coat acrylic oil-bound distemper of approved quality colour and shade of IITB approved manufacturer to old/new surfaces including step ladder etc, complete.	5000.00		Sqm	
11	Providing and applying two coats of acrylic oil-bound distemper of IITB approved manufacturer & quality colour and shade as per product specification on old/new surfaces including removing the old peeled off neeru finish /pop/ existing luster paint / water proofing cement paint/wall paper by scappring, sand papering and preparing the surface smooth, necessary repairs to scratches including step ladder etc complete	15200.00		Sqm	
12	Providing and applying one priming coat of IITB approved brand/manufacturer over steel and other metal surfaces etc including preparing the surface by thoroughly cleaning oil, grease, dirt, and other foreign matter with wire brushing, fine fire steel wool, and sand paper, stepladder as per manufacture specification etc. Complete.	1500.00		Sqm	
13	Providing and applying one priming coat of IITB approved brand/manufacturer to wood and wood based surface etc including preparing the surface by thoroughly cleaning oil, grease, dirt, and other foreign matter with wire brushing, fine fire steel wool, and sand paper, step ladder as per manufacture specification etc. Complete.	3000.00		Sqm	

14	Providing and applying two coats of synthetic enamel paint of IITB brand/manufacturer and colour to new/old structural steel work and wood work in buildings and workshops including as per manufacture specification step ladder if necessary, cleaning and preparing surfaces by solvent, degreasing and derusting by manual scrapping/mechanically by sand blasting/shot blasting flame cleaning/by chemical methods etc,complete.	4500.00		Sqm	
15	Providing and applying two coats of exterior Acrylic exterior paint of Asian,Nerolac,Berger,Delux make including exterior primer of above mentioned make, approved colour and shade to the plastered surface as per manufacturers specification including preparing the surface Including step ladder etc, complete	500.00		Sqm	
16	Disposing debris, loose stones, boulders, concrete pieces broken and dry leaves etc. collected and stacked as directed including loading in trucks, transporting out of IIT Campus including obtaining all approval of BMC competants authorities for disposing off on to their approved location. The debris are to be removed from site within 48 hours from stacking (30% voids will be deducted from actul stack measurement/ truck measurement for debrises, loose stones, boulders etc.).	15.00		Cum	
17	Providing and applying acrylic synthetic plaster (Dura plaster) of IITB approved make manufacturer over existing cement plaster or concrete surface including removing existing paint/synthetic plaster to receive the acrylic synthetic plaster as per manufacturer specification Including all the necessary tools & plants,stepladder etc, complete all as directed by Engineer in charge.	90.00		Sqm	
18	Providing and laying super fluid micro concrete of IITB approved manufacturer for exposed RCC member like slab,column,beam,staircase pardi,lintel mixed proportion as per manufacturers specification at any floor providing and fixing plywood form work in line and level, cleaning, curing etc. complete. the compressive strength of super fluid micro concrete should be 25N/sqmm .including working platform	5000.00		Kg	

19	Providing and fixing in position steel TMT bar reinforcement of various diameters for slabs, beams, columns,chajjas, lintels, pardies, etc. as per by Engineer Incharge including cutting, bending, hooking the bars,cost of welding rod for welding to existing reinforcement and supporting as required complete.	20.00		Kg	
20	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	50.00		Sqm	
21	Providing and applying Dr.Fixit Dampguard Classic(Base + Hardener) as per manufactures specification including scrapping applying first coat of Dampguard Classic over that applying Damguard Classic Putty followed by Scrapping and after that applying final coat of Damgurad Classic etc.complete all as directed.	50.00		Sqm	
22	Wall painting of two coats with acrylic emulsion paint , having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.	4600.00		Sq.m	
				Total Amount Rs.	
				Add GST 18%	
				Net Amount Rs.	
				Say Rs.	

Note: 1. Contractor should cover furniture/Resident's belonging with plastic sheet to avoid damage and stain while carrying out the work. 2. Contractor has to take permission of residents/Estate office engineer prior to removal and redo the polymer/SFMC work. 3. Contractor has to ensure that all deployed workers should be in proper safety gears during work. If any lapses are noticed, contractor will be fined Rs.5000/-for each incident noticed.4. Contractor should cover the tile flooring area with plywood sheet while chipping work or breaking work of ceiling to avoid the damages to the existing tiles flooring.

Amount in Rs. _____

_____

Signature & Stamp of the contractor